


Storm Piping Schedule - Bldg. B*					
Pipe	Size/Mat.	Length	US Inv.	DS Inv.	Slope
AA	15" HDPE	100.0'	1003.00	998.00	13.00%
BB	12" HDPE	80.0'	1001.00	996.00	8.33%
CC	10" HDPE	30.0'	1000.00	1000.65	1.50%
DD	8" HDPE	30.0'	1005.55	1005.10	1.50%
EE	10" HDPE	16.8'	1005.10	1004.85	1.50%
FF	10" HDPE	30.0'	1004.85	1004.40	1.50%
GG	8" HDPE	30.0'	1006.00	1005.70	1.00%
HH	8" HDPE	30.0'	1005.70	1005.40	1.00%
II	10" HDPE	30.0'	1005.40	1005.10	1.00%
JJ	10" HDPE	30.0'	1005.10	1004.80	1.00%
KK	12" HDPE	30.0'	1004.80	1004.50	1.00%
LL	12" HDPE	13.3'	1004.50	1004.37	1.00%
MM	8" HDPE	30.0'	1006.00	1005.40	2.00%
NN	8" HDPE	30.0'	1005.40	1004.80	2.00%
OO	8" HDPE	30.0'	1004.80	1004.20	2.00%
PP	10" HDPE	30.0'	1004.20	1003.60	2.00%
QQ	10" HDPE	30.0'	1003.60	1003.00	2.00%
RR	12" HDPE	30.0'	1003.00	1002.40	2.00%
SS	12" HDPE	30.0'	1002.40	1001.80	2.00%
TT	12" HDPE	30.0'	1001.80	1001.20	2.00%
UU	12" HDPE	30.0'	1001.20	1000.60	2.00%
VV	15" HDPE	30.0'	1000.60	1000.00	2.00%
WW	15" HDPE	30.0'	1000.00	999.40	2.00%
XX	15" HDPE	30.0'	999.40	998.80	2.00%
YY	18" HDPE	75.0'	998.80	990.00	11.70%

Drawn By	CDB
Checked	EJB
Approved	EJB
Job No.	214013
1" = 60' Scale	7-20-16 Date
 C201 Sheet No.	